

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T46 & 47NR 11 W

--- L u s e --- COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 2, 3, 34, 35

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 13" W. Pine (S 2 NBT) S 54° E 116 Links

16" W. Pine Stump (NBT) S 12° W 64 Links

20" W. Pine Stump (NBT) N 39° W 78 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established by Double proportionate measure from corners 1 mile north; 1 mile south; 1 mile west and 1/2 mile east. No evidence of original corner.

Corner was placed and witnessed May 11, 1960 with Frank J. Bray.

SURVEYORS SEAL

SIGNED

*Billy D. Buckler*  
REGISTERED LAND SURVEYOR

Billy D. Buckler

DATE 5/23/60