

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T46-47 NR 11 W ..

L u c e COUNTY

DESCRIPTION OF CORNER ~~Section corner common to Section 3, 4, 33, 34~~

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 15" W. Pine (S 3 NPT) S 4° E 229 Links

Re-marked original B.T.

W. Pine Stump S 34° W 41 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from probable B.T. bearing S 34° W 41 Links. Found possible traces of stake in soil. Checked south to Hemlock line tree and Section corner. Position checks with corners to east and west along township line. Corner lies 1 1/4 chains north of road.

Corner was placed and witnessed May 11, 1960 with Frank J. Bray.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 5/23/60
REGISTERED LAND SURVEYOR
Billy D. Buckler