

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
 Luce Co. Five Corners

| FOR CORNERS OF-- | LOCATED IN-- | CORNER CODE NUMBER |
|--------------------------------------|--|---|
| 1. PUBLIC LAND SURVEY | T. _____ N. _____ E. _____ S. _____ R. _____ W. _____ | 16, Sec. 4 9, Sec. 4 2, Sec. 4 6, Sec. 4 13, Sec. 4 |
| 2. PROPERTY CONTROLLING IN SECTION | 4, T. 46 N. _____ E. _____ 8, R. 11 S. _____ W. _____ | _____ |
| 3. MISCELLANEOUS PROPERTY IN SECTION | T. _____ N. _____ E. _____ S. _____ R. _____ W. _____ | _____ |
| 4. LOT NO. _____ | RECORDED PLAT _____ | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on 4-4-1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 16, Sec. 4 East 1/16 Cor. on South Side, Sec. 4.
- 2, Sec. 4 East 1/16 Cor. on North Side, Sec. 4.
- 9, Sec. 4 East 1/16 Cor. Sec. 4.
- 6, Sec. 4 NE 1/16 Cor. Sec. 4.
- 13, Sec. 4 SE 1/16 Cor. Sec. 4.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 16, Sec. 4 Corner placed midway and on line bet. Sec. Cor. to East and 1/4 Cor. to West.
- 2, Sec. 4 Corner placed midway bet Sec. Cor. to East and 1/4 Cor. to West.
- 9, Sec. 4 Corners placed by proper sub-division of a standard Section.
- 6, Sec. 4 Corner placed by proper sub-division of a standard Section.
- 13, Sec. 4 Corner placed by proper sub-division of a standard Section.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Placed 1" pipe with 4" aluminium cap at all corners.

- 16, Sec. 4 Bearings: 16" W. Pine S60°W 61.0' and 20" W. Pine S10°W 81.2'
- 2, Sec. 4 Bearings: 20" W. Pine 140°W 143.9' and 8" J. Pine S40°W 86.7'
- 9, Sec. 4 Bearings: 10" Maple S59°E 60.4' and 12" W. Pine N3°E 48.8'
- 6, Sec. 4 Bearings: 8" W. Pine S77°W 14.8' and 8" W. Pine S1°E 9.9'
- 13, Sec. 4 Bearings: 22" W. Pine S52°E 101.3' and 10" W. Pine S27°E 96.4'

SIGNED BY Billy D. Buckler DATE 6/8/73

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____