

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
 Luce Co. Two Corners.

rule

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>46</u> ^{N.} S. , R. <u>11</u> ^{E.} W.	<u>E-3</u> <u>D-3</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____, S., R. _____	E. _____ W. _____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____, S., R. _____	E. _____ W. _____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on 3-13 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
 Both corners originally set by Francis Coleman, D.S. in 1851.

- E-3 Sec. Cor., 4-5-8-9.
Bearings were: Maple 14", N55°W, 17 lks. and Y. Birch 30", S51°E, 10 lks.
- D-3 Quarter Corner, bet. Secs: 5-8.
Bearings were: Maple 12", N60°E, 9 lks. and hemlock 12", S38°W, 25 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- E-3 Corner re-established by proportionate measure, bet. corners; 1 mile East; 1 mile West; and 1 mile North.
- D-3 Corner re-established midway and on line bet. two Section Corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Placed 1" pipe with 4" aluminium cap at both corners.

- E-3 New Bearings:
28" Hemlock, S85°W, 41.3' and 12" Red Maple, N5°E, 20.2'
- D-3 New Bearings:
22" Hemlock, N67°W, 18.7' and 16" hemlock, N35°E, 16.6'

SIGNED BY Billy D. Buckler DATE 5/3/74

SURVEYOR'S MICHIGAN REGISTRATION NO. 3887



FOR STATE AND UNITED STATES AGENCIES:
 SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR