

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Luce Co.

Two Corners

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>46</u> ^{N.} S. , R. <u>11</u> ^{W.} E.	K-2 K-3
2. PROPERTY CONTROLLING IN SECTION _____	T. _____, S. _____, R. _____, E. _____, W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____, S. _____, R. _____, E. _____, W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 8/7 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
Corners placed originally by Francis Coleman, D.S. in 1851.

- K-2 Quarter Cor. bet. Sec's. 1-2. Bearings were: W. Pine 20", N46°W, 43 lks. and W. Birch 18", S26°E, 5 lks.
- K-3 Section Corner 1-2-11-12. Bearings were: Hemlock 10", N36°E, 17 lks. and Y. Birch 10", S42°W, 30 lks.


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-2 Corner replaced from one probable witness; a W. Pine stump in proper position. Distance checks to Section Corner 1/2 mile North.
- K-3 Corner re-established by proportionate distance East and West, one mile to Section Corners, and at record distance from 1/4 Corner 1/2 mile North. Found distance East to hill checks.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Placed 1" pipe with 4" aluminium cap at all corners.

- K-2 New Bearings: 15" Hemlock, S32°W, 27.8' and 9" Soft Maple, N60°W, 18.1'. Corner lies 33.0' East of road.
- K-3 New Bearings: 15" Hemlock, S80°W, 31.6' and 8" Soft Maple, N57°E, 13.8'

SIGNED BY Billy D. Buckler DATE 8/22/74



SURVEYOR'S MICHIGAN REGISTRATION NO. 8387

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____