

#12

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Locality:

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>11W</u>	<u>LS</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on September 16, 1993, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(LS) Quarter Corner common to Sections 12-13. Corner previously restored in 1974 by Billy D. Buckler RLS as follows: Placed 1" pipe with 4" aluminum cap. New Bearings: 10" Spruce N10E 26.4', 8" W. Pine N69W 45.2'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(LS) Recovered Buckler's monument at record bearing and distance from the White Pine NBT, now 12" dia. Marked a blaze at BH on the W. Pine. The Spruce NBT is dead and down. Marked 3 new witness trees and placed measuring nails with tags in all 4.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(LS) Found 1" pipe with 4" MDNR cap
Blazed, scribed, and set measuring nails
with tags in the following NBTS:
8" Balsam N60E 22.95' "1/4S NBT"
8" Spruce S25W 17.1' "1/4S NBT"
10" Maple West 28.3' "1/4S NBT"
12" W. Pine N69W 45.3' "1/4S NBT"



Signed by Stephan J. Szyszkoski Date 1-27-94
Surveyor's Michigan License No. 33986