

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>46N</u> R <u>11W</u>	<u>G3</u>	
	T <u>    </u> R <u>    </u>	<u>    </u>	
	T <u>    </u> R <u>    </u>	<u>    </u>	
	T <u>    </u> R <u>    </u>	<u>    </u>	
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>	
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>	
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>	
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Sep 18 2002

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

**A. Description of original monument and accessories and/or subsequent restoration:**  
 (G3) Corner common to Sections 3-4-9-10. 1851- Established by Francis Colman: S57°E...71.29 Hemlock 10"...79.46 Sug. 14 cor of secs 3,4,9, & 10. Fir 10 N12W 11 links. 1960- Remonumented by Billy D. Buckler RLS: This corner was replaced as set by H. Lawrence, Registered Surveyor. Found scribed wood post, in place with Hemlock line tree 10.+ chains north of corner. Line tree is down and in fair condition. Corner lies 1 chain north of road. Mr. Buckler set a 1" pipe with 4" brass cap and the following NBTs: 8" Soft Maple N03W 43 links, 10" Soft Maple S50E 50 links.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(G3) The original corner tree and BT were not recovered. Found the 1960 monument as described, with a brass Michigan Dept. of Conservation tablet, in good condition, and at substantial record bearing and distance from the two 1960 NBTs, both in good condition with overgrown blaze. Distances north (79.93 M, 79.46 R) and east (79.72 M, 79.25 R) are both 47 links longer than the GLO record. Bearing north (N57°25'W M, N57°W R) checks very well with the record. I accept the monument and make new witnesses as described below.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(G3) Found 1" ID I. pipe with 4" brass MI Dept. of Conservation cap. Blazed, scribed and set measuring nails in:  
 20" Maple S47E 33.45' "S10" \*  
 12" Maple N03E 28.5' "S4" \*  
 6" Maple N42W 26.05' "S4 NBT"  
 6" Spruce S59W 29.6' "S9 NBT"  
 Old wood post adjacent. Bearings are magnetic. Distances are to nail with tag. \* denotes 1960 BT.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 12/10/02