

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>11W</u>	<u>A5</u>
	T <u>46N</u> R <u>12W</u>	<u>M5</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 08/25/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A5) Section corner common to Sections 7-18 T46N-R11W and Sections 12-13 T46N-R12W. 1841 - Established by Wm.A.Burt Deputy Surveyor. Set post. Spruce 6" N73E 18 links, Spruce 5" N47W 50 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A5) The original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner by single proportionate measurement to the original record, on the Range line between Section corner 5280.46' north and Township corner 21121.84' south. From the position thus established, I found a 1" iron pipe with wood post, not of record, possibly placed by John McLaren for Cleveland-Cliffs Co. in the 1950s, S06W 41.2' distant which I did not accept as marking the position for the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A5) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.  
 Set measuring nail with MDNR tag in the side of:  
 10" Spruce N69E 5.6' mrkd "S6 NBT"  
 7" Balsam S15W 14.35' "S12 NBT"  
 10" Tamarack S63W 22.15' "S12 NBT"  
 13" Spruce N05E 26.25' "S6 NBT"  
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 09/25/2008  
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities