

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

|                                       |                           |               |
|---------------------------------------|---------------------------|---------------|
| <u>Luce</u><br>(County)               | Located In:               | Corner Code # |
| 1. Public Land Survey                 | T <u>46N</u> R <u>11W</u> | <u>B5</u>     |
|                                       | T _____ R _____           | _____         |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____   | _____         |
|                                       | S _____ T _____ R _____   | _____         |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____   | _____         |
|                                       | S _____ T _____ R _____   | _____         |
| 4. Lot No. _____, Recorded Plat _____ |                           |               |
| 5. Private Claims _____               |                           |               |

Register of Deeds Stamp & File Number

|    |    |    |    |    |    |    |   |   |   |   |   |   |   |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
| 1  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  | ●  |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

I, Stephan J. Szyszkoski, in a field survey on 06/30/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(B5) Quarter corner common to Sections 7-18. 1851 - Established by Francis Coleman Deputy Surveyor on the Section line between Section corners 40.00 chains east and 41.02 chains west. Set post. Cedar 10" N55E 12 links, Fir 7 S31W 24 links. 1974 - Billy D. Buckler RLS reestablished the corner "by extending line thru two Cedar line trees, to East of Corner. Found small stream, 25 links East of corner as record indicates. No evidence of Cedar Witness identified". Set 1" pipe with 4" aluminum cap. 12" Cedar S70W 31.7', 14" Cedar S20E 29.4'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B5) The original post and accessories were not recovered. Found the 1974 monument in good condition and at record bearing and distance from the 1974 witnesses, both in good condition. Accepted the monument as a careful and faithful reestablishment of the position of the original corner. Distances to adjacent Section corners were found to be 2638.30' to east and 2713.33' to west. The center of a small creek is about 17' east of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B5) Found 1" ID I. pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 16" Cedar S17E 30.15' mrkd "1/4S" 1974 NBT  
 18" Cedar S73W 32.15' do do  
 14" Cedar N08W 13.45' mrkd "1/4S NBT"  
 20" twin Cedar N76E 32.0' do  
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 09/25/2008  
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities