

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>11W</u>	<u>C3</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3			●										
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 07/30/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C3) Corner common to Sections 5-6-7-8. 1851 - Established by Francis Coleman Deputy Surveyor. Set post. Hemlock 9 N71W 10 links, Hemlock 14 S54E 36 links. 1971 - corner recovered by Billy D. Buckler RLS: "Re-witnessed 2" iron pipe placed by unknown surveyor. Pipe lies on NW corner of a pine plantation. Found no evidence of original corner or witnesses". 50" W.Pine stump S8E 36.3', 14" B. Cherry S62W 62.4'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C3) Found a 2" ID iron pipe and a 1" ID iron pipe with Michigan Department of Natural Resources cap adjacent at record bearing and distance from the 1971 witness B.Cherry, in good condition with overgrown blazes. The position of the monument fits reasonably well with the original record to corners 1 mile south and 1 mile west and I accept same as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C3) Fd. 2" I.pipe with 1" ID I.pipe MDNR mon. adjacent. Drove MDNR mon. into 2" pipe. Set measuring nail with MDNR tag in the side of:
 10" R.Pine S83E 22.0' mrkd "S8 NBT"
 12" R.Pine S44E 8.6' do
 14" R.Pine S16E 23.1' do
 18" Cherry S65W 62.9' mrkd "S7" 1971 NBT
 5" W.Pine N14W 51.35' mrkd "S6 NBT"
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 09/25/2008
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities