

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 46N R 11W	B3
	T _____	_____
	T _____	_____
2. Property Controlling in Section	S T _____	_____
	S T _____	_____
	S T _____	_____
3. Miscellaneous Property in Sec.	S T _____	_____
	S T _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3	●												
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 08/27/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

(B3) Quarter corner common to Sections 6 and 7. 1851 - Established by Francis Coleman Deputy Surveyor on the Section line between Section corner 40.00 chains east and Section corner 39.34 chains west. Set post. Fir 8" N29E 46 links, Beech 3" S22W 24 links. 1971 - Remonumented by Billy D. Buckler RLS: "replaced a wood post set by John McLaren 1952. Found no original evidence." 1" pipe with 4" aluminum cap. 20" Soft Maple N50E 44.2', 11" Soft Maple N37W 47.5'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(B3) The original post and accessories were not recovered. The 1971 monument and its accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner by proportionate measurement to the original record, on the Section line between Section corners 2589.44' west and 2632.89' east.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(B3) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 4" Maple S77E 8.85' mrkd "1/4S NBT"  
 15" Cherry S35E 28.7' do  
 9" Cherry S45W 16.35' do  
 16" Y.Birch N10E 33.6' do  
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 09/25/2008  
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities