

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 7 T 46N R 11W	1
	S 7 T 46N R 11W	8
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3	●											
4	●	7	8	9	10	11	12					
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Stephan J. Szyszkoski, in a field survey on 08/21/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(1-Sec. 7) West 1/16 corner between Sections 6 and 7. Not established in the original survey.

(8-Sec. 7) West 1/16 corner, Section 7. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(1-Sec. 7) Established the corner 20 chains, proportionate to the original record, west of Quarter corner B3 and on the Section line between B3 (1316.44' east) and Section corner A3 (1273.00' west).

(8-Sec. 7) Established the corner on the E-W 1/4 line of Section 7 between Center of Section 1319.66' east and Quarter corner 1331.56' west, being 20 chains, proportionate to the original record, west of the Center of Section.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(1) Set 5/8"x24" rebar with plastic MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 16" Hemlock S30E 23.15' mrkd "W1/16 BT"
 11" W.Spruce N14E 31.8' do
 9" Maple N80W 10.05' do
 13" Hemlock S63W 35.2' do
 Bearings are magnetic.

(8) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 10" Hemlock East 2.9' mrkd "W1/16 BT"
 16" Hemlock N53E 19.55' do
 18" Hemlock N04W 11.35' do
 19" W.Pine S61W 24.6' do
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 09/25/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

