

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>46N</u> R <u>11W</u>	<u>C4</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on 06/30/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C4) Quarter corner common to Sections 7 and 8. 1851 - Established by Francis Coleman Deputy Surveyor midway and on the Section line between Section corners 40.00 chains north and south. Set post. Fir 6" N53E 35 links, Fir 8" S66W 19 links. 1974 - Corner reestablished by Billy D. Buckler RLS midway and on line between Section corners. Set 1"ID I.pipe with 4" aluminum cap. W.Pine Cluster N45W 55.3', 16" Tamarack N08W 61.1'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C4) Found the 1974 monument in good condition and at record bearing and distance from the 1974 NBTs, both in good condition. Found the monument to be located S09W 0.51' from the midway position intended in 1974 and accepted same as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C4) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 18" W.Pine clump N42W 55.2' mrkd "1/4S" 1974 NBT
 20" Tamarack N09W 61.7' do do
 6" Tamarack S82W 6.85' mrkd "1/4S NBT"
 8" W.Pine N36E 14.55' do
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 09/25/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities