

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>46N</u> R <u>11W</u>	<u>A4</u>
	T <u>46N</u> R <u>12W</u>	<u>M4</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 08/25/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A4) Quarter corner common to Section 7 T46N-R11W and Section 12 T46N-R12W. 1841 - Established by Wm.A.Burt Deputy Surveyor midway and on the Range line between Section corners 40.00 chains north and south. Set post. Fir 8" N21E 33 links, Fir 8" N15W 12 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A4) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner midway and on the Range line between Section corners 2640.23' north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A4) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.  
 Set measuring nail with MDNR tag in the side of:  
 23" twin Hemlock N20E 22.7' mrkd "1/4S NBT"  
 19" Hemlock N67W 16.75' do  
 17" Maple S31W 15.45' do  
 14" twin Maple S62E 9.75' do  
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 09/25/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities