

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>11W</u>	<u>C5</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 06/30/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C5) Corner common to Sections 7-8-17-18. 1851 - Established by Francis Coleman Deputy Surveyor. Set post. Spruce 6" N43W 22 links, Spruce 8" S50E 24 links. 1974 - Reestablished by Billy D. Buckler RLS "by extending line thru two original Cedar Line Trees, 805.2' and 2059.2' West of corner. Found a Tamarack stump blazed, N70E, 17.0' from corner". Set 1"ID I.pipe with 4" aluminum cap. 14" Cedar N46W 38.7', and scribed 4" Balsam at corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C5) The original post and accessories were not recovered. Found the 1974 monument in good condition and at record bearing and distance from the Cedar NBT NW, in good condition, and the Tamarack stump, no marks visible. The 4" Balsam "at corner" is now a stump. Accepted the monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C5) Found 1"ID I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 14" Cedar N75W 38.65' mrkd "S7 NBT"
 16" Cedar N43W 39.1' mrkd "S7" 1974 NBT
 10" B.Spruce N11E 7.75' "S8 NBT"
 7" Maple S63E 19.8' "S17 NBT"
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 09/25/2008
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities