

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46 NR. 12 W.

----- Luce ----- COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 4, 5, 8, 9, -----

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass cap -----

WITNESSES TO CORNER 10" W. Pine Stamp - S 38 F - 46 Links -----

14" W. Pine Stamp - N 58 F - 102 Links -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established, by double proportionate measurement, by Forestry Division survey crew, while making a partial resurvey of this Township. One probable original B.T. still in place, badly burned.

Corner was placed and witnessed June 23, 1952.

SURVEYORS SEAL

SIGNED James C. [Signature] DATE 3/15/53
REGISTERED LAND SURVEYOR