

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T46-47 NR 12 W ..

----- Luce ----- COUNTY

DESCRIPTION OF CORNER 1/4 Section Corner between Sections 31 and 6 -----

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap -----

WITNESSES TO CORNER 9" Jack Pine ----- N 52° W ----- 47½ links -----

9" Jack Pine ----- S 52° W ----- 40 links -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced 1/4 Corner from one probable Yellow Pine B.T. (badly burned).

Old blazes on White Pine stub facing East and West, in line with corner.

Distance checks with good Section Corner to East.

Corner placed and witnessed August 3, 1956.

SURVEYORS SEAL

SIGNED Billy D. Buckler ----- DATE 8/10/56 -----  
REGISTERED LAND SURVEYOR