

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46 NR. 12 W

L u c e COUNTY

DESCRIPTION OF CORNER ~~Section corner common to Sections 15, 16, 21, 22~~

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 16" Red Pine (S 21 NBT) S 8° W 146 Links

6" Red Pine (S 15 NBT) S 27° E 95 Links

5" Red Pine (S 22 NBT) S 34° E 82 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. This corner was re-established by proportionate measure between section corners 1 mile north and line tree 21.94 chains south and on a true bearing of N 0° 06' E from the line tree. Found old blazes to west, also found a W. Pine at site of the corner with blazes, axe marks which have grown over. Could not determine where this tree had stood.

Corner was placed and witnessed June 3, 1960 with Daniel Bonner, Assistant D.F.

SURVEYORS SEAL

SIGNED *Billy D. Buckler* DATE 9/14/60
REGISTERED LAND SURVEYOR
Billy D. Buckler