

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 46 N.R. 12W


Luce COUNTY

DESCRIPTION OF CORNER 1/4 Cornere bet. Sec's 14-15

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 4/25/68

WITNESSES TO CORNER.....7" W. Pine (1/4 S NBT) N 70W 56.2'



CIRCLE CORNER REGISTERED

6" SoftMaple (1/4 S NBT) N 48E 30.3'

AND

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

This corner replaced from one original witness; a W. Pine stump bearing N 22 E 15 Links Found Notch and remains of lower blaze. Corner found by Bruce Veneberg, Ass't Forester.

Corner located checks with line tree to North and other corners in the vicinity.

Cor. lies 6chs South of Road

**SURVEYOR'S SEAL**

SIGNED Billy J. Buckler DATE 6/28/68  
REGISTERED LAND SURVEYOR