

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46 N.R. 12W


Luce COUNTY

DESCRIPTION OF CORNER 1/2 Corner bet Sec's 10-15

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 4/25/68

WITNESSES TO CORNER..... 13" Soft Maple (1/2 S NBT) N 51 W 22.3'



14" Hemlock (1/2 S NBT) S 18 W 22.8'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced from one Beech witness bearing N 54E 32links Tree green and in fair condition. Both faces have been chopped out several years ago.

Corner lies on an E-W fence line. Found a Soft Maple with old blazes facing corner. Found a scribed post with an Iron Fence Post 63.0' East of Corner.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 6/28/68
REGISTERED LAND SURVEYOR