

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46 N. R. 12W


Luce COUNTY

DESCRIPTION OF CORNER Sec. Cor. common to Secs 10-11-14-15

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 4/25/68

WITNESSES TO CORNER..... 13" Hard Maple (S15 NBT) S 47W 26.1'



14" Beech (S14 NBT) S 67E 14.6'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner placed at proportionate distance between; $\frac{1}{4}$ corner $\frac{1}{2}$ mile South and a line tree ~~to the~~ North and at Record distance (32.19 chs) from a Beech line tree to West Found Several blazed lines intersecting corner location. Found yellow birch with a large blaze facing corner

Corner lies 3 chs North of a woods road.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 6/28/68
REGISTERED LAND SURVEYOR