

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46N N. R. 12W


Luce COUNTY

DESCRIPTION OF CORNER $\frac{1}{4}$ corner between Secs. 21-28

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 6-11-69

WITNESSES TO CORNER..... 4" Tamarack ($\frac{1}{4}$ S NBT) S30°E 7.9'



5" B. Spruce ($\frac{1}{4}$ S NBT) West 8.8'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced from one Tamarack witness tree, bearing S74°E, 43 links. Found log down and badly deteriorated, with face, scribe marks and calloused overgrowth. Found bottom of blaze on stump.

Found no evidence of use.

SURVEYOR'S SEAL

SIGNED *Billy D. Buckler*
Billy D. Buckler DATE 7-25-69
REGISTERED LAND SURVEYOR