

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Luce Co.

3 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY_____	T. <u>46</u> N. <u>12</u> E. <u>W.</u>	C-6	REGISTER OF DEEDS STAMP AND FILING NUMBER
2. PROPERTY CONTROLLING IN SECTION <u>14</u>	T. <u>46</u> N. <u>12</u> E. <u>W.</u>	12-Sec.14 3-Sec.14	
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. _____		
4. LOT NO. _____, RECORDED PLAT _____			
5. PRIVATE CLAIMS _____			

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 5-19 & 5-31 & 5-3, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- C-6** Quarter Corner bet. Sec's. 17-18, set by Francis Coleman D.S. in 1851.
Bearings were: Hemlock 12, N36°E, 20 lks. and Cedar 10, S46°W, 21 lks.
- 12-Sec.14** South 1/16 Corner of Section 14.
- 3-Sec.14** North 1/16 Corner on Westside of Section 14.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:


- C-6** Corner replaced at wood post set by unknown parties. Position checks with corners to North and South.
- 12-Sec.14** Corner placed midway between Center Corner to North and $\frac{1}{4}$ Corner to South.
- 3-Sec.14** Corner placed midway between Section Corner to North and $\frac{1}{4}$ Corner to South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 1" pipe with 4" aluminium cap at all corners.

- C-6** New Bearings: 10" Cedar, S2°E, 23.9' and 12" Cedar, S55°W, 38.5'.
- 12-Sec.14** Bearings: 8" Tamarack, N29°W, 19.0' and 8" Cedar, N20°E, 32.6'.
- 3-Sec.14** Bearings: 6" Maple, N26°W, 19.7' and 6" Beech, S48°E, 35.8'.

SIGNED BY Billy D. Buckler DATE 9-11-78
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. _____