

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Luce

|                                       |                           |               |
|---------------------------------------|---------------------------|---------------|
| (County)                              | Located In:               | Corner Code # |
| 1. Public Land Survey                 | T <u>46N</u> R <u>12W</u> | <u>C1</u>     |
|                                       | T ___ R ___               | _____         |
|                                       | T ___ R ___               | _____         |
|                                       | T ___ R ___               | _____         |
| 2. Property Controlling<br>in Section | S ___ T ___ R ___         | _____         |
|                                       | S ___ T ___ R ___         | _____         |
| 3. Miscellaneous<br>Property in Sec.  | S ___ T ___ R ___         | _____         |
|                                       | S ___ T ___ R ___         | _____         |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Sep 14 2004

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

|    |    |    |    |    |    |    |   |   |   |   |   |   |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A  | B  | C  | D  | E  | F  | G  | H | I | J | K | L | M |
| 1  |    |    |    |    |    |    |   |   |   |   |   |   |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

**A. Description of original monument and accessories and/or subsequent restoration:**  
 (C1) Corner common to Sections 5-6 T46N-R12W and Sections 31-32 T47N-R12W. 1841: Established by John Burt. Set post. Y.Pine 12 N62E 89, Y.Pine 12 N46W 103. 1851: Additional BTs by Francis Colman: W.Pine 16 S34E 320 links, Y.Pine 12 S24W 246 links. 1949: J.L. Halbach, MDNR forester notes: "Large fancy iron - scribed post. NE Red Pine stump has plain face. Only 1/2 of NW Red Pine stump remains - 1/2 face. 1952: Remonumented by Dean C. DeLaMater. Set 1" pipe with 4" brass cap. "corner was pointed out to be by J.Halbach... Three original B.T.s still in place, fair condition". New witnesses: 14" Red Pine S70W 37 links, 12" Red Pine N33E 106 links.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**  
 (C1) Found the 1952 monument, with top bent over, at record bearing and distance from the remaining 1952 witness of record. The Red Pine SW is in good condition. The Red Pine NE was not recovered. Removed the 1952 monument and installed a new one in its place. The center of an E-W road is 18' south of the corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(C1) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set nails with tags in:  
 20" R.Pine S74W 24.6' no new marks \*  
 3" J.Pine N58W 40.7' no marks  
 3" J.Pine N24E 17.0' do  
 3" J.Pine S33W 59.1' do  
 Cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. \* denotes 1952 NBT.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 3/15/05