

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Luce

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>46N</u> R <u>12W</u>	<u>D1</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Sep 14 2004

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

(D1) Quarter corner common to Section 5 T46N-R12W and Section 32, T47N-R12W. 1841: Established by John Burt. Set qr. section post. Y.Pine 22 N45W 15, W.Pine 30 N55E 7. 1956: Remonumented by Billy D. Buckler at record bearing and distance from the remains of the original bearing trees. Set 1" Iron pipe with 4" brass cap. 14" Red Pine S85E 133 links, 12" Red Pine S12W 65 links.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(D1) Found the 1956 monument, with top bent over, at record bearing and distance from the 1956 witness trees. The R.Pine SW is in good condition. The R.Pine SE is a dead stub 10' high. I roughly measured distances east and west to adjacent section corners and found this monument to be midway between them. Removed the 1956 monument and replaced it with a new monument. From the corner, the center of an E-W road is south 10', and the center of a road north is 20' west.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(D1) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set nails with tags in:  
 24" R.Pine S15W 43.0' mrkd "1/4S" \*  
 14" R.Pine N48W 53.2' "1/4S NBT"  
 12" J.Pine N16E 22.9' do  
 12" R.Pine S89E 76.55' do  
 Bearings are magnetic. Distances are to nail with tag. \* denotes 1956 NBT.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 3/15/05