

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luca</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>12W</u>	<u>62</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Sep 13 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G2) Quarter corner common to Sections 3 and 4. 1851 - Established by Francis Colman, Deputy Surveyor: S03'E Corrected between Sections 3 & 4 ...39.00 Begin to descend bank 25 ft.; 40.40 Set qr. Sec. post on SW declivity of bank. W.Pine 10 N54E 21 links, Spruce 11 S60W 30 links; 40.90 Foot of bank C SSE; 42.51 Tahquamenaw River 80 L C SSE ...80.40 Section corner. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G2) The original post and accessories were not recovered. Reestablished the corner by single proportionate measurement to the original record, on the Section line between Section corners 2625.19' north and 2599.20' south. From the position thus established, I found a 1.25" ID iron pipe, not of record, N68E 14.4' distant (horizontal distance).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G2) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
 26" W.Pine S12W 28.82' no markings
 16" W.Pine S12E 24.18' do
 6" W.Birch S80E 13.98' do
 7" Spruce N58W 16.17' do
 Bearings are magnetic. Distances are to nail with MDNR tag. All distances were measured on the slope.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 12/13/06

For the Michigan Department of Natural Resources, Office of Land and Facilities