

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>12W</u>	<u>63</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Aug 15 2006

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(G3) Corner common to Sections 3-4-9-10. 1851 - Established by Francis Colman, Deputy Surveyor: S03'E corrected between Sections 3 & 4 ...80.40 Set post corner of Sections 3,4,9,10. W.Pine 18 N18E 16 links, W.Pine 12 S56W 25 links on eastern declivity of bank. 1952 - Dean C. DeLaMater RLS perpetuated the original position stating in the record "Corner had been previously located and perpetuated by H.C. Lawrence, Registered Land Surveyor. One original B.T. still in place, poor condition. Set 1" pipe with 4" brass cap. Witnesses: 9" W. Birch N05E 88 links."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G3) Recovered the 1952 monument in good condition and at record bearing and distance from the 1952 NBT W.Birch. Neither original B.T. was recovered. Accepted the monument as a careful and faithful perpetuation of the position of the original corner and made new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G3) Found 1" pipe with 4" brass MI Dept. of Conservation cap. Set measuring nails in:  
 3" Spruce N88W 8.95' no markings  
 7" Maple S77E 7.17' mrkd "1/4S NBT"  
 5" Maple N40W 18.75' do  
 10" W.Pine N15E 26.5' do  
 Bearings are magnetic. Distances are to nail with MDNR tag and are measured on the slope.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 12/13/06

