

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
Luce Co. One Corner

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>47</u> N. <u>X</u> , R. <u>9</u> W.	<u>E-1</u>
2. PROPERTY CONTROLLING IN SECTION_____	, T. _____ N. _____ E. _____ S., R. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	, T. _____ N. _____ E. _____ S., R. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 11/20, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

E-1 Sec. Cor. 4-5, on North Boundary of Township.
Corner set by John Burt, D.S. in 1841. Bearings were: Sugar 12", N63°W, 37 lks and Beech 12", N9°W, 21 lks. and Y. Birch 10", S23°E, 16 lks. and Sugar 8", S10°W, 16 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

E-1 Corner replaced from remains of three original witnesses; A Hard Maple still growing, face is chopped out; a Beech stub broken off, 6' high, old chopping; a Y. Birch stump, has turned out and partially rotted. Found bottom of post in soil. Found a largesquared post on ground near by, believed set by H. Lawrence, RLS before 1940. Area recently logged.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1 Placed 1" pipe with 4" aluminium cap at corner.

New Bearings: 12" W. Spruce, East, 19.8'.

SIGNED BY Billy D. Buckler
Billy D. Buckler
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

DATE 2-15-77



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____