

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 47 N.R. 9 W


Luce COUNTY

DESCRIPTION OF CORNER Section Corner for Secs. # 22-23-26-27

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 10/20/1965

WITNESSES TO CORNER..... 8" J. Pine (S23 NBT), N 45° E, 47 lks.



7" Tamarack (S27 NBT), S 77° W, 92 lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established by double proportionate measurement between Section Corners 1 mile North and East and 3 miles West and 1/4 Corner 1/2 mile to South.

SURVEYOR'S SEAL

*Frank J. Bray*  
SIGNED Frank J. Bray DATE 11/23/1965  
REGISTERED LAND SURVEYOR