

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47 N.R. 9 W


Luce COUNTY

DESCRIPTION OF CORNER Section Corner for Secs. 21-22-27-28

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 10/20/1965

WITNESSES TO CORNER..... 8" W. Pine (S21 NBT), N 86° W, 17 lks.



6" Spruce (S22 NBT), N 44° E, 19 lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established by double proportioned measurement between Section Corners 2 miles to West and 1 mile to East and South and 1/4 Corner 1/2 mile to North.

SURVEYOR'S SEAL

Frank J. Bray
SIGNED Frank J. Bray DATE 11/23/1965
REGISTERED LAND SURVEYOR