

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47 N.R. 9 W


 Ince COUNTY

DESCRIPTION OF CORNER Section Corner for Secs. 2-3-10-11

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 8/25/65 with I. Ribick

WITNESSES TO CORNER..... 22° W, Pine (S2 NBT), N 58° E, 49 lks.



10° S, Maple (S10 NBT), S 40° W, 44 1/2 lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was reestablished by double proportionate measurement between Line Tree to South, 1/4 Corner to North and Section Corners to East and West.

SURVEYOR'S SEAL

Frank J. Bray
SIGNED Frank J. Bray DATE 11/23/1965
REGISTERED LAND SURVEYOR