

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION



# LAND CORNER RECORD

T. 47-48 N.R. 9 W

Luce COUNTY

DESCRIPTION OF CORNER Section Corner for Secs. 2-3, T47N R9W & 34-35, T48N R9W

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 8/18/65 with L. Rubick

WITNESSES TO CORNER..... 8" H. Maple (S2 NBT), S 73° E, 10 lks.



8" H. Maple (S34 NBT), N 84° W, 16 1/2 lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established by placing on line and the proportioned distance between 1/4 Corner 1/2 mile to West and Town Corner 2 miles East.

SURVEYOR'S SEAL

Frank J. Bray  
SIGNED Frank J. Bray DATE 11/19/1965  
REGISTERED LAND SURVEYOR