

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 47 N.R. 9 W


Line COUNTY

DESCRIPTION OF CORNER N 1/16 Corner for Secs. 2/1

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 8/24/65 with L. Rubick

WITNESSES TO CORNER..... 8" Hemlock (N 1/16 BT), N 26° E, 26 Lks.



10" H. Maple (N 1/16 BT), S 31° E, 30 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was placed on Line and the proportioned distance between 1/4 Corner to South and Section Corner to North.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 11/19/1965  
REGISTERED LAND SURVEYOR