

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47 N.R. 9 W


Luce COUNTY

DESCRIPTION OF CORNER W 1/16 Corner between Secs. 12-13

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 9/3/65 with L. Rubick

WITNESSES TO CORNER..... 7" J. Pine (W 1/16 BT), S 57° E, 61½ Lks.



9" J. Pine (W 1/16 BT), S 13° W, 19½ Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was placed midway and on Line between 1/4 Corner to East and Section Corner to West.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 11/23/1965
REGISTERED LAND SURVEYOR