

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 47 N.R. 9 W


Irce COUNTY

DESCRIPTION OF CORNER 1/4 Corner for Secs. 3/2

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 8/18/1965 with L. Rubick

WITNESSES TO CORNER..... 6" W. Pine (1/4S NBT), N 18° W, 19 Lks.



5" Cedar (1/4S NBT), S 70° E, 09 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was replaced from Tamarack 4", S 33° E, 12 Lks. which has overgrowth of notch and Spruce stump bottom under moss N 34° W, 14 Lks. both Original BT's.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 11/19/1965  
REGISTERED LAND SURVEYOR