

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47 N.R. 9 W


Ince COUNTY

DESCRIPTION OF CORNER Section Corner for Secs. 14-15-22-23

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 8/27/1965 with L. Rubick

WITNESSES TO CORNER..... 9" J. Pine (S23 NBT), S 86° E, 10 Dcs.



5" J. Pine (S22 NBT), S 41° W, 26 Dcs.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established by double proportionate measurement between 1/4 Corners 1/2 mile West and 1/4 miles South and Section Corners 1 mile to North and to East.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 11/23/1965
REGISTERED LAND SURVEYOR