

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47 N.R. 9 W


Luce COUNTY

DESCRIPTION OF CORNER Section Corner for Secs. 11-12-13-14

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 6/3/65 with R. Hinds

WITNESSES TO CORNER..... 6" Jackpine (S12 NBT), N 38° E, 29 Dcs.



5" Tamarack (S14 NBT), S 51° W, 28 Dcs.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established by double proportionate measurement between 1/4
Corners 1/2 mile to West and South and Section Corners 1 mile to North and East.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 11/19/1965
REGISTERED LAND SURVEYOR