

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47 N. R. 9W


Luce COUNTY

DESCRIPTION OF CORNER Section Corner common to Secs. 28-29-32-33

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 9/11/63

WITNESSES TO CORNER..... 5" Tamarack (S32 NBT) S5°W 03 Lks.



5" Tamarack (S29 NBT) West 16 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established by Double Proportionate measure from Corners 1 mile South; 2 miles West; $2\frac{1}{2}$ miles North and $3\frac{1}{2}$ miles East. No evidence of Original Corner. Position checks with Stream to East.

SURVEYOR'S SEAL

SIGNED *Billy D. Buckler*
BILLY D. BUCKLER
REGISTERED LAND SURVEYOR

DATE 7/31/1964