

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 47 N. R. 9W


Luce COUNTY

DESCRIPTION OF CORNER Section Corner common to Secs. 25-26-35-36

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 9/11/63

WITNESSES TO CORNER..... 5" B. Spruce (S25 NBT) North 46 Lks.



12" W. Pine (S35 NBT) S78°W 111 Lks.

AND

CIRCLE CORNER REGISTERED

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

This Corner was re-established by Double Proportionate measure from Corners  $\frac{1}{2}$  mile East; 1 mile North; 1 mile South and 5 miles West. Found old squared Jackpine stub 12 Links South-West of Corner.

SURVEYOR'S SEAL

SIGNED *Billy D. Buckler*  
BILLY D. BUCKLER  
REGISTERED LAND SURVEYOR

DATE 7/31/1964