

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47 N. R. 9W


Luce COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Secs. 29-30

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 7/7/63

WITNESSES TO CORNER..... 12" W. Pine (1/2 S MBT) S11°E 58 Lks.



12" Jackpine (1/2 S MBT) N40°E 40 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established midway and on line between two Section Corners.
No evidence of Original Corner. Corner lies on South slope of a Pine ridge.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler
BILLY D. BUCKLER
REGISTERED LAND SURVEYOR

DATE 7/32/1964