

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47 N.R. 9W


Luce COUNTY

DESCRIPTION OF CORNER Section Corner common to Secs. 29-30-31-32

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 7/5/63

WITNESSES TO CORNER..... 8" Jackpine (S31 NBT) S40°W 19 Lks.



8" Jackpine (S29 NBT) N30°E 48 Lks.

7" B. Spruce (S32 NBT) S80°E 16 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established on a straight line and by proportionate distance between Section Corners 1 mile North and 1 mile South. Distance checks well to Section Corner 1 mile West and a stream to East.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler
BILLY D. BUCKLER
REGISTERED LAND SURVEYOR

DATE 8/3/1964