

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47 N. R. 9W


Luce COUNTY

DESCRIPTION OF CORNER Section Corner common to Secs. 15-16-21-22

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 10/16/63 with L. Rubick, Forestry Aide

WITNESSES TO CORNER..... 4" Jack Pine (S15 NBT) N6°E 33 Lks.



4" B. Spruce (S15 NBT) N86°E 45 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established by Double Proportionate measure from Corners, $\frac{1}{2}$ mile South; 1 mile North; $\frac{1}{2}$ mile East and $1\frac{1}{2}$ miles West. Found no evidence of Original Corner.

SURVEYOR'S SEAL

SIGNED *Billy D. Buckler* DATE 7/31/1964
BILLY D. BUCKLER
REGISTERED LAND SURVEYOR