

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47 N.R. 9^W


Luce COUNTY

DESCRIPTION OF CORNER Section Corner common to Secs. 27-28-33-34

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 9/11/63

WITNESSES TO CORNER..... 5" Tamarack (S27 NBT) N35°E 09 lks.



5" Tamarack (S34 NBT) S30°E 15 lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established by Double Proportionate measure from Corners
3 miles West; $2\frac{1}{2}$ miles East; $1\frac{1}{2}$ miles North and 1 mile South.

SURVEYOR'S SEAL

SIGNED *Billy D. Buckler*
BILLY D. BUCKLER
REGISTERED LAND SURVEYOR

DATE 7/31/1964