

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47N N. R. 9W


Luce COUNTY

DESCRIPTION OF CORNER $\frac{1}{4}$ Corner between sections 25-36

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 7-24-62 with I. Rubick, aide

WITNESSES TO CORNER..... 10" W. Pine ($\frac{1}{4}$ S NBT) N59°W, 29 links



10" Hemlock ($\frac{1}{4}$ S NBT) N71°E, 28 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from one cedar B.T. (green) bearing S15°W, 10 links. Found scribe marks plain on lower face. Also found post apparently set by H. Lawrence, registered land surveyor with several signatures. Corner lies 50 links north of logging road.

SURVEYOR'S SEAL

SIGNED *Billy D. Buckler* DATE March 7, 1963
REGISTERED LAND SURVEYOR

Billy D. Buckler