

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T 47N R 9W	H12
	T _____ R _____	_____
2. Property Controlling in Section	S 34 T 47N R 9W	8
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 03/25/2008 do hereby state  
03/27/2008  
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(8-Sec. 34) West 1/16 corner, Section 34. Not established in the original survey.

(H12) Center of Section 34. Not established in the original survey. 1965 - T.J.McLaren for Cleveland-Cliffs Iron Company set post and iron "on corrected line at midpoint between established 1/4 corners". R.Pine 8 S53E 5.2', R.Pine 11 N25W 7.5'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(8-Sec. 34) Established the corner midway and on a straight line between Quarter corner 1319.47' west and Center of Section 1319.47' east.

(H12) Recovered a 1" square iron rod, presumably the 1965 monument. I did not accept it as marking the position for the corner. The monument is not located at the record position, and the 1965 method used to determine the corner position is not proper. The monument does not appear to have been relied upon as the corner by local land owners. There is no evidence of improvements in the area and the 1965 position was not marked by any accessories indicating its acceptance as a title corner by any party. I established the corner at the intersection of straight lines connecting opposite 1/4 corners. The 3/4" sq. iron is 29.1' West and 4.0' South of the position thus established.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(8) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
5" B.Spruce S31E 8.73' mrkd "W1/16 BT"  
4" B.Spruce S39W 5.88' do  
4" B.Spruce N35W 28.75' do  
4" B.Spruce S64E 47.6' do  
Bearings are magnetic.

(H12) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
16" R.Pine N48E 6.48' mrkd "C1/4 BT"  
12" R.Pine S37W 11.58' do  
14" R.Pine S66E 14.48' do  
1" sq. iron rod S87W 29.44'  
Bearings are magnetic.

Signed by *Stephan J. Szyszkoski*  
Surveyor's Michigan License No. 33986

Date 04/09/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

