

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 47N R 9W	H13
	T 47N R 9W	G13
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Stephan J. Szyszkoski, in a field survey on 03/11/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

(H13) Quarter corner common to Section 34 T47N-R09W and Section 3 T46N-R09W. 1962 - Reestablished by single proportionate measurement, midway and on the Township line between Section corners, by Billy D. Buckler RLS. Set 1" pipe with 4" aluminum cap. 5" Tamarack N70W 13 links, 4" Tamarack (bearing omitted) 54 links.

(G13) Corner common to Sections 33-34 T47N-R09W and Sections 3-4 T46N-R09W. 1962 - Reestablished by Billy D. Buckler RLS by single proportionate measurement to the original record, midway and on the Township line between Section corners. Set 1" pipe with 4" aluminum cap. 7" Soft Maple N36E 37 links, 14" Soft Maple S44W 52 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H13) Found the 1962 monument, in good condition, at record bearing and distance from the two Tamarack NBTs (the omitted bearing being N16E), both in good condition with old blazes. The monument is substantially at the record midway position between Section corners and I accept same as a careful and faithful reestablishment of the position of the original corner.

(G13) Found the 1962 monument in good condition and at record bearing and distance from the Soft Maple NBT SW, in good condition. The Soft Maple NBT NE was not recovered. Made new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H13) Found 1" ID I. pipe with 4" alum. MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
 7" Tamarack N68W 8.8' mrkd "1/4S" 1962 NBT
 7" Tamarack N16E 36.2' mrkd "1/4S NBT" do
 7" Tamarack S46W 27.65' do
 4" Maple S26E 9.9' do
 Bearings are magnetic.

(G13) Fd. 1" ID I. pipe with 4" alum. MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
 16" Maple S50W 34.4' open blazes (1962 NBT)
 10" B. Spruce S80W 25.55' mrkd "S4 NBT"
 6" Maple S15E 27.4' "S3 NBT"
 6" W. Pine S81E 34.3' do
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 04/09/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities