

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 47N R 9W	G12
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on 03/17/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G12) Quarter corner common to Sections 33 and 34. 1964 - Reestablished by Billy D. Buckler RLS midway and on line between Section corners 1/2 mile to north and south. Set 1" Iron pipe with 4" aluminum cap. 14" Tamarack S50E 13.5 links, 12" Tamarack S66W 22 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G12) Recovered the 1964 monument in good condition, at record bearing and distance from the 1964 NBTs. The 1964 monument is S15W 6.2' from the proportionate position intended in 1964. The magnitude of this error far exceeds the observed error in Mr. Buckler's determination of the other 3 1/4 corners on Section 34. Consequently, I judged this position to have been monumented erroneously due to some blunder. I removed the 1964 monument and reestablished the corner at the midway position intended by Mr. Buckler in 1964, on the Section line between corners 2636.86' north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G12) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 13" Tamarack S19E 13.7' mrkd "1/4S" 1964 NBT  
 15" Tamarack S57W 19.05' do do  
 7" Tamarack N84W 13.45' mrkd "1/4S NBT"  
 11" Maple N50E 24.4' do  
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 04/09/2008  
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities