

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

| | | |
|---------------------------------------|-------------|---------------|
| Luce | Located In: | Corner Code # |
| (County) | | |
| 1. Public Land Survey | T 47N R 9W | H9 |
| | T 47N R 9W | G10 |
| | T | |
| 2. Property Controlling in Section | S T | |
| | S T | |
| | S T | |
| 3. Miscellaneous Property in Sec. | S T | |
| | S T | |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Register of Deeds Stamp & File Number

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, Stephan J. Szyszkoski, in a field survey on H9 03/26/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(H9) Quarter corner common to Sections 22 and 27. 1965 - Frank J. Bray RLS reestablished the corner midway and on line between Section corners. Set 1"ID I.pipe with 4" aluminum cap. 7" Tamarack S56W 6 links, 5" Tamarack S75E 35.5 links.

(G10) Quarter corner common to Sections 27 and 28. 1965 - Frank J. Bray RLS reestablished the corner midway and on line between Section corners. Set 1"ID I.pipe with 4" aluminum cap. 5" Tamarack S87W 3.5 links, 7" J.Pine N70E 47 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H9) Recovered the 1965 monument in good condition and S23W 0.47' from the midway position intended in 1965. The 1965 NBTs were recovered in good condition and at record bearing and distance. Accepted the monument as a careful and faithful reestablishment of the position of the original corner.

(G10) Found the 1965 monument in good condition and at record bearing and distance from the 1965 NBT SW, in good condition. The NBT J. Pine NE was not recovered. Its remains may be obscured by deep snow. The monument is N19E 1.4' from the midway position intended in 1965 and I accept same as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H9) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 7" Tamarack S75E 24.7' mrkd "1/4S" 1965 NBT
 9" Tamarack S56W 4.1' do do
 5" Tamarack N36E 4.6' mrkd "1/4S NBT"
 9" Tamarack N37W 29.55' do
 Bearings are magnetic.

(G10) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 4" Tamarack S07W 24.15' mrkd "1/4S NBT"
 6" Tamarack S86W 2.6' old blazes 1965 NBT
 4" B.Spruce S58E 6.95' mrkd "1/4S NBT"
 5" Tamarack N30E 20.4' do
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 09/08/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities