

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T 47N R 9W	G9	
	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S _____ T _____ R _____		
	S 27 T 47N R 9W	2	
	S _____ T _____ R _____		
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		
	S _____ T _____ R _____		
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9							●	●					
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on 2 03/26/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(G9) Corner common to Sections 21-22-27-28. 1965 - Frank J. Bray RLS reestablished the corner by double proportionate measurement between Section Corners 2 miles to West and 1 mile to East and South, and 1/4 corner 1/2 mile to North. Set 1" I.pipe with 4" aluminum cap. 8" W.Pine N86W 17 links, 6" Spruce N44E 19 links.

(2-Sec. 27) East 1/16 corner between Sections 22 and 27. 1965 - Frank J. Bray RLS established the corner midway and on line between Section corner to East and 1/4 corner to West. Set 1" I.pipe with 4" aluminum cap. 20" Y.Pine N58E 117 links.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(G9) Recovered the 1965 monument in good condition and at record bearing and distance from the NBT W.Pine NW, now 12" DBH in good condition. The Spruce NBT NE was not recovered.

(2-Sec. 27) Recovered the 1965 monument in good condition and at record bearing and distance from the 1965 BT, now standing dead. Accepted the monument as a careful and faithful establishment of the position of the corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(G9) Fd. 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 12" W.Pine N86W 11.5' mrkd "S21" 1965 NBT  
 6" Tamarack S46E 6.9' "S27 NBT"  
 8" W.Pine S13W 24.45' "S28 NBT"  
 10" W.Pine N47E 41.25' "S22 NBT"  
 Bearings are magnetic.

(2) Fd. 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 5" W.Pine N76E 83.55' mrkd "E1/16 BT"  
 6" B.Spruce N60E 74.2' do  
 5" Tamarack S81W 83.15' do  
 4" Tamarack S07E 84.35' do  
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 09/08/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities