

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T 47N R 9W	110
2. Property Controlling in Section	S 27 T 47N R 9W	3
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims	3 03/19/2008	

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on 110 03/24/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(3-Sec. 27) North 1/16 corner between Sections 27 and 28. 1965 - Established by Frank J. Bray RLS midway and on line between Section corner north and Quarter corner south. Set 1"ID I.pipe with 4" alum. cap. 4" Tamarack S79W 246 links, 6" J.Pine N45E 197 links.

(I10) Quarter corner common to Sections 26 and 27. 1962 - Billy D. Buckler RLS remonumented the corner at the position of a wood post, found in accord with probable original BT remains. Set 1" pipe with 4" aluminum cap. 5" J.Pine S70E 38 links, 5" J.Pine N50E 46 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(3-Sec. 27) Recovered the 1965 monument in good condition and at record bearing and distance from the 1965 NBTs, both now dead. The monument is N35W 1.3' from the midway position intended in 1965 and I accept same as a careful and faithful establishment of the position of the corner.

(I10) Recovered the 1962 monument in good condition and at record bearing and distance from the 1962 witnesses, both in good condition. The monument is located S54E 6.6' from the midway position between Section corners north and south and I accept same as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(3) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 3" Tamarack N52E 13.6' no blazes
 3" Tamarack N88E 12.7' do
 3" Tamarack N84W 16.6' do
 3" Tamarack N63W 28.3' do
 Bearings are magnetic.

(I10) Fd. 1"ID I.pipe with 4" alum. cap. Set measuring nail with MDNR tag in the side of:
 6" J.Pine S34E 25.7' mrkd "1/4S NBT"
 7" J.Pine S78W 31.1' do
 12" J.Pine S66E 25.35' "1/4S" 1962 NBT
 10" J.Pine N52E 30.75' do do
 Bearings are magnetic.

Signed by *Stephan J. Szyszkoski*
 Surveyor's Michigan License No. 33986

Date 09/08/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities